### **NC STATE UNIVERSITY**

**Department of Forest Biomaterials** 

Campus Box 8005, Dan Allen Dr. Raleigh, NC 27695-8005 USA

919.515.5807 919.515.6302(fax)

Hodges Wood Products Laboratory 919.515.2850

# A Report to Kastamonu

from

North Carolina State University Wood Products Laboratory

on

## NALFA's Laminate Surface Swell Test – Assembled Joint

April 2024

Project Number: WPL-24-1976

Principal Investigator

Lynday Campbell

Lyndsey Campbell

Department of Forest Biomaterials Rm.110 Hodges Wood Products Lab Campus Box 8005, Dan Allen Drive Raleigh, NC 27695-8005 USA 919-515-2881

Wn tachsarvicas@no

Wp\_techservices@ncsu.edu

**NC STATE UNIVERSITY** 

WPL-24-1976

April 2024 Kastamonu p. 2

### **IMPORTANT**

- These tests were conducted according to the procedures described in NALFA's Laminate Surface Swell Test Assembled Joint.
- The test procedures and standards were designed for laminate flooring, and their use with other products may produce misleading or irrelevant results.
- We do not certify a manufacturer's laminate flooring. We report only on the results of a given sample of laminate flooring which has been submitted to our laboratory for testing.
- The name of the University is not to be used in any type of advertising or promotional efforts.
- We have undertaken testing of laminate flooring as an independent testing laboratory largely
  as a service to the laminate flooring industry. However, our main purpose is that of
  education and research, which means that we cannot always respond quickly to requests for
  testing.

NC STATE UNIVERSITY

WPL-24-1976

April 2024 Kastamonu p. 3

Kastamonu submitted one (1) sample for testing according to the test method NALFA Laminate Surface Swell Test – Assembled Joint modified to a duration of 72 hours total.

Sample coded as follows:

Sample	Identification
1	FLOORPAN/ARTFLOOR URBAN

Results to follow.

April 2024 Kastamonu p. 4

### **TEST RESULTS**

### NALFA LAMINATE SURFACE SWELL TEST – ASSEMBLED JOINT (72 HOURS TOTAL)

The NALFA Laminate Surface Swell- Assembled Joint Test is reported quantitatively and qualitatively. The quantitative measurement is reported as the final average thickness swell in both Point 1 and Points 2-4, but the performance criteria is based on Points 2-4. They are expressed as difference in the Recovery Swell measurement and Wet Swell measurement. The qualitative measurement is based on the grading of the Recovered joints enclosed in the PVC ring where the water was located.

Surface Swell - Results Summary							
			+48 hours (72 hours total)				
Sample	Identification	Replicate	Recovered Qualitative Rating	Measured Recovered Average			
3	FLOORPAN/ARTFLOOR	1	1	0.1			
	URBAN	2	1	0.1			

#### Grade:

- 1 = No change No noticeable change in edge swell or panel surface lift
- Slight swelling Slight swelling, small ridge along one or more joints, very little if any panel surface lift.
- 3 = Moderate Noticeable edge swelling and some panel surface lift extending away from joint
- 4 = Objectional Severely raised edge and swelling extending noticeably under the panel surface.
- 5 = Invalid Test Water leaked out of the ring, leaving no continuous film of water inside the ring (this grade is given even if there is no swell of the edge joint)

### MINIMUM PERFORMANCE VALUES FROM THE STANDARD

NALFA Topical Moisture (summary table)			Results	Minimum Performance
1	Recovered Qualitative Rating	1-5		≤2
1	Measured Recovered Average (mm)	mm		≤0.3

\*Minimum performance values only based on points 2-4 (P2-4)

WPL-24-1976

April 2024 Kastamonu p. 5

### TEST RESULTS

### +48 HOURS (72 HOURS TOTAL)

Specimen 3A- Quantitative Results								
Position	Time water added:							
	Initial height (mm)	Wet Height	Wet Swell	Recov. Height	Recov. Swell			
1	-0.05	0.25	0.3	0.07	0.12			
2	0.02	0.24	0.22	0.11	0.09			
3	0.07	0.31	0.24	0.18	0.11			
4	0.14	0.34	0.2	0.21	0.07			
Average	0.05	0.29	0.22	0.14	0.09			
	Initial Thickness Avg	Wet Height Avg	Wet Swell Avg	Recov. Height Avg	Recov. Swell Avg			
Specimen 3	A- Qualitative Result							
Wet	1							
Recov.	1							
		Specimen 3B- Qu	antitative Resul	ts				
Position		Time water added:						
	Initial height (mm)	Wet Height	Wet Swell	Recov. Height	Recov. Swell			
1	-0.20	0.07	0.27	-0.09	0.11			
			_					
2	-0.22	0	0.22	-0.13	0.09			
3	-0.04	0.19	0.23	0.06	0.1			
4	-0.17	0.01	0.18	-0.12	0.05			
Average	-0.16	0.07	0.21	-0.07	0.08			
	Initial Thickness Avg	Wet Height Avg	Wet Swell Avg	Recov. Height Avg	Recov. Swell Avg			
		1						
Specimen 3	BB- Qualitative Result							
Wet	1							
Recov.	1							